ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

: ವರದಿ :

ವಿಷಯ : Improvements and Maintenance of culverts at Mallasandra Colony and surrounding area in ward no 13 Shettyhalli Sub Division

Job Code:-

Est Cost: Rs. 10.00 Lakhs

****

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ದಾಸರಹಳ್ಳಿ ವಲಯ, ಶೆಟ್ಟಿಹಳ್ಳಿ ಉಪವಿಭಾಗದ ವಾರ್ಡ್ ನಂ.13, ಮಲ್ಲಸಂದ್ರದ Improvements and Maintenance of culverts at Mallasandra Colony and surrounding area in ward no 13 Shettyhalli Sub Division ಕಾಮಗಾರಿಯು 2018–19 ನೇ ಸಾಲಿನಲ್ಲಿ ಬಿಬಿಎಂಪಿ ಆಯವ್ಯಯದ ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ ಪಿ–1771 ಅಡಿಯಲ್ಲಿ ರೂ 10.00 ಲಕ್ಷಗಳಿಗೆ ಮಂಜೂರಾಗಿದ್ದು, ಸದರಿ ಕಾಮಗಾರಿಗೆ ಜಾಬ್‌ಸಂಖ್ಯೆ ದೊರೆತಿರುವುದಿಲ್ಲ. ಆದರೆ ಮುಖ್ಯ ಅಭಿಯಂತರರು, ದಾಸರಹಳ್ಳಿ ವಲಯ ಮತ್ತು ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ ರವರು ತುರ್ತಾಗಿ ಸದರಿ ಕಾಮಗಾರಿಗೆ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ಸಲ್ಲಿಸುವಂತೆ ಸೂಚಿಸಿರುತ್ತಾರೆ.

ವಾರ್ಡ್ ನಂ.13 ಮಲ್ಲಸಂದ್ರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಬರುವ ಮಲ್ಲಸಂದ್ರ ಕಾಲೋನಿ ಮತ್ತು ಸುತ್ತಮುತ್ತಲ ಪ್ರದೇಶದ ರಸ್ತೆಗಳಲ್ಲಿ ಬರುವ ಕಲ್ವರ್ಟ್‌ಗಳ ಅಭಿವೃದ್ಧಿ ಮತ್ತು ನಿರ್ವಹಣೆ ಕಾಮಗಾರಿಗಾಗಿ 2018–19 ನೇ ಸಾಲಿನ ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ ದರ ಪಟ್ಟಿ ಅನುಸಾರ ದರಗಳನ್ನು ಅಳವಡಿಸಿಕೊಂಡು ಈ ಕೆಳಗಿನ ಅಂಶಗಳೊಂದಿಗೆ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ತಯಾರಿಸಲಾಗಿದೆ.

1. Earthwork excavation by manual means for roads, drains.
2. Providing and laying plain cement concrete of mix 1:3:6.
3. Providing and laying plain/reinforced cement concrete .
4. Providing TMT steel, etc.,

ಮೇಲ್ಕಂಡ ಅಂಶಗಳನ್ನು ಒಳಗೊಂಡಂತೆ ಅಂದಾಜು ಪಟ್ಟಿ ರೂ.10.00 ಲಕ್ಷಗಳಿಗೆ ತಯಾರಿಸಲಾಗಿದ್ದು, ಸದರಿ ಅಂದಾಜು ಪಟ್ಟಿಗೆ 2018–19 ನೇ ಸಾಲಿನ ಬಿಬಿಎಂಪಿ ಆಯವ್ಯಯದ ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ ಪಿ–1771 ಅಡಿಯಲ್ಲಿ ಆಡಳಿತಾತ್ಮಕ ಅನುಮೋದನೆ ಹಾಗೂ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಬೇಕಾಗಿ ಕೋರಿ ಅಂದಾಜು ಪಟ್ಟಿ ಸಲ್ಲಿಸಿದೆ.

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ವಾರ್ಡ್ ನಂ–13

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಶೆಟ್ಟಿಹಳ್ಳಿ ಉಪವಿಭಾಗ, ದಾಸರಹಳ್ಳಿ ವಲಯ
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಬೆಂಗಳೂರು

Scanned by CamScanner

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

ne of Work: Improvements and Maintenance Of Culverts at Mallasandra Colony and Surrounding a in Ward No.13 Shettyhalli Sub Division.

Est .Cost Rs.10.00 Lakhs

Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
KSRRB 300-3 Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3 Page No 142/ Item No 19.1/ PWD SR 2018-19								
Mallasandra colony		3	5.80	1.70	1.00	29.58		
		4	5.40	2.00	1.00	43.20		
		2	4.50	2.00	1.00	18.00		
	Cum					**90.78**	**207.60**	**18845.93**
KSRRB M2100-10 Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
Mallasandra colony		3	5.80	1.70	0.15	4.44		
		4	5.40	2.00	0.15	6.48		
		2	4.50	2.00	0.15	2.70		
	Cum					**13.62**	**5421.90**	**73830.01**
Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200, including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271)								
Mallasandra colony								
Bottom raft		3	5.80	1.50	0.15	3.92		
		4	5.40	1.80	0.15	5.83		
		2	4.50	1.80	0.15	2.43		
Wall		6	5.80	0.25	0.80	6.96		
		8	5.40	0.25	0.80	8.64		
		4	4.50	0.25	0.80	3.60		
For Deck Slab		3	5.80	1.50	0.30	7.83		
		4	5.40	1.80	0.30	11.66		
		2	4.50	1.80	0.30	4.86		
	Cum					**55.73**	**7070.20**	**394029.32**
SRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in osition, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever ecessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM mplete as per specifications. Specificatio(I No-28.8.2,P No-229)								
onsider 90 kg /Cum For Culvert			55.73	90.00		5015.79		
	Ton's				Say	**5.02**	**72326.98**	**362776.94**
						Total construction cost		**849482.20**
						Add GST Charge 12%		**101937.86**
						Sub Total		**951420.06**
						Tender premium 5%		**47571.00**

Scanned by CamScanner

Miscellaneous and unforseen Charges	1008.93
TOTAL	1000000.00

(RupeesTen Lakhs Only)

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary

2 The Estimate is prepared as per the PWD SR 2018-19

Sub Total

This area comes under BBMP limits.

This work is not included in any other estimate.

Asst Engineer
Ward No-13

Asst Executive Engineer
Shettyhalli Sub-Division
BBMP

Executive Engineer
Dasarahalli Zone
BBMP

ನಂ. EE/DD/AS/102 ದಿನಾಂಕ : 19-20

ರೂ. Rs 10.00 lakhs

Rupees Ten lakhs only

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/64/18-19 ದಿನಾಂಕ : 30/01/2019

ರೂ. Rs Ten lakhs only

(10.00) Lt

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner